Pine Bluff Street Department

190

DAKOTA ST.

WESTGATE LN.

UTAH ST.

WISCONSIN ST.

BRENTWOOD DR.

BELMOOR AVE.

NEBRASKA ST.

OHIO ST.

OUTLET CANAL

Pine Bluff Wastewater Utility

Liquor

E. 16TH AVE.

Roberts Brothers Tire Service

Splash Car Wash

Broadmoor Shopping Center

HARDING AVE.

Admiral Benbow Ditch

Carpenters Produce Fish Market

Advance Auto Parts

Varco Homes

Mini-Storage Buildings

Texaco

VFW Post 4455

Hot Rods

Music Mart

Pope Furniture

Regency Inn

Bad Bobs

E. 17TH AVE.

Thunder Lanes Bowling Center

Carrington Electric

American Red Cross

Hallmark Manor Ditch

N. BELAIR DR.

Greenfield Mobile Home Park - Private

E. 18TH AVE.

LEVEE

LEVEE

BELLE MEADE DR.

W. BELAIR DR.

S. BELAIR DR.

W & A Manufacturing Company

Pitts Drain

Outlet Canal

E. 20TH AVE.

Commerce Road Ditch

Southeast Junior High School

Ditch 'B'

ARKANSAS STATE HIGHWAY NO. 190

NOTES

The Outlet Canal. Plan and Profile. U.S. Army Corps of Engineers, Vicksburg District . Local Protection - Pine Bluff File No. O-7736 Date: September 26th, 1952. Located in Drawer DD.

Harding Avenue. (Arkansas State Highway 190) Arkansas State Highway and Transportation Department JOB 2471 Plan and Profile. Fiscal Year 1956. Located in Drawer I.

Broadmoor Subdivision, Unit 1. Plans For Street and Drainage Improvements. A.E. Heagler - Consulting Engineer. Date: April, 1958. Located in Drawer " Subdivisions A-B"

Harding Avenue. From Wisconsin Street to U.S. Highway 425. AHTD JOB 2798. Plan and Profile. Date: 1976. Located in Drawer I.

Pitts Drain. Corps of Engineers Selected Plan. Urban Water Management Study. Pine Bluff Comprehensive Flood Control Plan. Date: August, 1979. On File.

Southeast Junior High School Drainage Improvement Project. The City of Pine Bluff Engineering Department. Date: February, 1988. Located in Drawer Y.

The Admiral Benbow Ditch Improvement Project. The Pine Bluff Street Department . Date: 1993. Located in Drawer Y. See Also " Broadmoor / Belmont Drainage Problem File. Cabinet 2, Drawer F.

Harding Avenue , From Main to Ohio. An Improvement Plan proposal by Grimes Consulting Engineers Inc. Date: April, 1990. Located in Drawer W. See Also " Half Size Plan" Drawer .

KEY TO SYMBOLS AND ABBREVIATIONS

→ = Direction of Flow ←→ = Break in Flow

→ Inlet with opening in side or back of box. Underground Stormwater Drainage Pipe

Junction Box beneath asphalt (inaccessible) X Structure Eliminated

VG = Valley Gutter CB = Catch Basin MH = Manholes GTI = Grated Top Type Inlet JB = Junction Box

RCB = Reinforced Concrete Box Culvert RCP = Reinforced Concrete Pipe CMP = Corrugated Metal Pipe

CMAP = Corrugated Metal Arch Pipe ACCMP = Asphalt or Bituminous Coated Corrugated Metal Pipe

w/FES = with Flared End Section

REVISIONS	
DATE	BY

CITY OF PINE BLUFF

STREET DEPARTMENT

TITLE

STORMWATER MANAGEMENT SYSTEM

SCALE: One Inch Equals 100 Feet +/-

DRAWN BY: Jeff

DATE: 1981 Photo 2003 Update

APPROVED BY

The Royal Society

MAP NUMBER

SW¼ SEC. 11, T6S, R9W